

ADDENDUM NO.4  
TO  
PLANS AND SPECIFICATIONS  
FOR  
EDITH KANAKA'OLE MULTI-PURPOSE STADIUM  
BUILDING ADDITION & IMPROVEMENTS  
JOB NO. PR-4166  
SOUTH HILO, HAWAI'I  
COUNTY AND STATE OF HAWAI'I

**NOTICE TO BIDDERS**

The items listed below are made a part of the current contract and shall govern the work, taking precedence over the previously issued specifications and drawings governing the particular item of work mentioned.

**REQUEST FOR INFORMATION/REQUEST FOR CLARIFICATION**

1. **QUESTION:** *Is the 4" clearance measured from the bottom of the bottom rail?  
The spec section notes the ornamental fence should be "Flush Top and Bottom"  
(no pickets extending).*

**RESPONSE:** Reference Sheet A6.1.1, Detail 1A and 1D; Yes, the 4" clearance is measured from the bottom of the bottom rail. Per the specification, the ornamental fence shall be "Flush top and bottom" (no pickets extending on the bottom). Drawings showing the pickets extending on the bottom past the bottom rail are in error.

2. **QUESTION:** *For Alt 2 and Alt 4, are conduits for lighting considered in an exterior or interior location?*

**RESPONSE:** The current Electrical Code shall dictate whether the conduits are considered interior or exterior.

3. **QUESTION:** *Will there be any extensions to the March 15, 2013 project completion requirement in the proposal?*

**RESPONSE:** No, the March 15, 2013 project completion date is firm. The contractor should take the accelerated schedule into account when bidding the project. The County will allow the contractor to extend daily work hours beyond the typical quitting time as long as work adheres to DOH codes regarding noise per specification section 01040 Coordination referenced below.

4. **QUESTION:** *Are there any PVC louvers in the project?*

**RESPONSE:** No, spec section 08900 should be disregarded.

**SPECIFICATIONS**

**ITEM NO. 1** – Specification Section 01040 Coordination

**ADD** paragraph D 1.03 Work Sequence.

- D. Contractor shall determine start, duration and end time of daily work schedule providing coordination with the Department for required inspections and shall adhere to DOH noise requirements.

**ITEM NO. 2** – Specification Section 01040 Coordination

**ADD** paragraph D 1.10 Contractor's Responsibilities.

- D. The Bidder shall include 20 (twenty) rain out days in its schedule with no effect to required March 15, 2013 completion date for the scope of work as described in the plans and specifications. Any rain out days greater than the 20 (twenty) provided for above shall be managed in accordance with the GRC's.

**ITEM NO. 3** – Specification Section 08900 Poly Vinyl Chloride (PVC) Jalousie Windows.

**REMOVE** Specification Section 08900 in its entirety.

**DRAWINGS**


ITEM NO. 1 –Sheet A6.1.1 Detail # 1. **ADD** 4" dimension from bottom of bottom rail to grade.

ITEM NO. 2 –Sheet A6.1.1 Detail # 1. **DELETE** 8" dimension from top of bottom rail.

ITEM NO. 3 –Sheet A6.1.1 Detail # 1. **DELETE** 4" dimension from bottom of pickets to grade, per specifications pickets do not extend below bottom rail.

ITEM NO. 4 –Sheet A6.1.1 Detail # 1. **ADD** note:

"Where the bottom rail passes over the concrete foundation at the steel column for Canopy A the bottom of the bottom rail shall not be more than 2" above the concrete."



Warren H. W. Lee, P.E., Director  
Department of Public Works  
County of Hawai'i

Date Issued: November 28, 2012

Please detach and execute the receipt below. Return immediately via facsimile (808) 961-8630 or mail to the Administration Office, Department of Public Works, County of Hawai'i at Aupuni Center, 101 Pauahi Street, Suite 7, Hilo, HI 96720-4224.

Receipt of Addendum No. 4 via website for the EDITH KANAKA'OLE MULTI-PURPOSE STADIUM BUILDING ADDITION & IMPROVEMENTS, Job No. PR-4166, South Hilo, Hawai'i, is hereby acknowledged.

Signed \_\_\_\_\_ Title \_\_\_\_\_

Firm \_\_\_\_\_ Date \_\_\_\_\_

EDITH KANAKA'OLE MULTI-PURPOSE STADIUM  
BUILDING ADDITION & IMPROVEMENTS  
JOB NO. PR-4166

**ADDENDUM NO.4**